SN5842



United States Department of the Interior

MINERALS MANAGEMENT SERVICE

GULF OF MEXICO OCS REGION

IMPERIAL OFFICE BLDG , 3301 N CAUSEWAY BLVD

PO BOX 7944

METAIRIE, LOUISIANA 70010-7944

High Island Area, East Addition. South Extension

IN REPLY REFER TO

ĽÉ-3-1 OCS-G 4305

January 20, 1983

ACTION

Transcontinental Gas Pipe Line Corporation

Right-of-Way

Pipeline Right-of-Way Abandoned

On March 13, 1980, Transcontinental Gas Pipe Line Corporation filed an application for a rightof-way two hundred (200) feet in width for the construction, maintenance, and operation of a ten (10) inch natural gas pipeline, 0.55 miles in length, from Transco Exploration Company's Platform "A" in Block A-284, to a subsea tie-in with the High Island Offshore System 30-inch pipeline (OCS-G 3302) in Block A-283, all located in High Island Area, East Addition, South Extension. By Action dated May 14, 1980, the application was approved and the right-of-way granted. Proof of construction was accepted on this pipeline on March 31, 1981.

On December 8, 1982, grantee requested relinquishment of the right-of-way in its entirety, as the pipeline has been abandoned in place in accordance with FORMERLY 43 CFR 3340.1(a) (6), NOW 30 CFR 256.89(a)(6).

Therefore, the right-of-way grant is relinquished and the pipeline abandoned in place effective as John L. Rankin

Pelinguished + Beban loned in Pace Acting Regional Manager

A-284

A-383 of December 8, 1982, the date the request for relinquishment was filed in this office.

Malas Mas

NOTED-SCHONEKAS

Jr 5842



A Subsidiary of Transco Companies Inc.

2700 Post Oak Boulevard

Dec 8 11 ou 14 192 MINERALS MAN TE 13 VII 60LT OF MEXICA DES RESION METAINIE: LOUISIANA

September 9, 1982

Mr. John L. Rankin, Minerals Manager New Orleans OCS Office Hale Boggs Federal Building 500 Camp Street, Suite 841 New Orleans, Louisiana 70130

RE: Relinquishment of Right-of-Way for 10" Natural Gas Pipeline, Block A-284 to Block 283, High Island Area, South Addition, OCS-G 4305

Dear Mr. Rankin:


Transcontinental Gas Pipe Line Corporation, as owner and holder, hereby releases, relinquishes, and surrenders to the United States of America, all of its rights, title, and interest in and to that certain pipeline right-of-way, OCS-G 4305, granted to Transcontinental Gas Pipe Line Corporation, by the United States of America, Bureau of Land Management, dated May 14, 1980, and described as follows to wit:

Right-of-way 200 feet in width for the construction, maintenance, and operation of a 10-inch natural gas pipeline 0.53 miles in length, from the Transco Exploration Company's "A" platform in Block A-284 to an underwater tap valve in Block A-283 all in the High Island Area, South Addition.

Transcontinental Gas Pipe Line Corporation requests relinquishment of the right-of-way in its entirety, as the pipeline has been abandoned in place in accordance with 43 CFR 3340.1 (a)(6).

Executed This 13th Day of September, 1982.

Senior Vice-President



10" NATURAL GAS PIPELINE REMOVED FROM SERVICE IN THE GULF OF MEXICO HIGH ISLAND AREA BLK A-284 TO BLK A-283 2 Nov '82 CALCOMP DATE 10/27/82 APPROVED BY 20G APPROVED BY JR N BATE 10/27/82 DATE 10-30- 12 CAMPAGE M. 74 CM SCALE 1 IN - 800 F1 18-80 21-12-2020 DATE SHEET 1 OF L

OFFSHORE TEXAS

DAR NO

DATED-28-82

D1-4A-002



BEST AVAILABLE COPY United States Department of the Interior

BUREAU OF LAND MANAGEMENT

0CS-G 4305 SNJ842

NEW ORLEANS OUTER CONTINENTAL SHELF OFFICE
HALE BOGGS FEDERAL BUILDING
500 CAMP STREET-SUITE 841
NEW ORLEANS, LA 70130

High Island Area, East Addition, South Extension

March 31, 1981

ACTION

Transcontinental Gas Pipe Line Corporation

: Right of Way for Pipe Line

Date of Permit: 5/14/80

: Decision Requesting Proof of

Construction Dated:

Proof of Construction Received: 3/23/81

Proof of Construction Accepted

The above-captioned permittee has submitted the evidence required by the law and regulations 43 CFR 3340.3(a). The proof of construction is hereby accepted and approved with minor deviations.

John L. Rankin

Manager

cc: U.S. Geological Survey (w/dwg. and reports)





びまれていたったったいで

A Subsidiary of Transco Companies Inc.

2700 South Post Oak Road P O Box 1396 Houston, Texas 77001 713-871-8000

March 19, 1981

Mr. John L. Rankin, Manager New Orleans OCS Office Bureau of Land Management Hale Boggs Federal Building 500 Camp Street, Suite 841 New Orleans, Louisiana 70130

Dear Mr. Rankin:

Reference: OCS-G 4305, 10" Pipeline from Block A-284 to

Block A-283 High Island Area, East Addition,

South Extension, Gulf of Mexico Line No. 1-1014, R/W 1, W.O. 5291.37

In compliance with the U. S. Department of Interiors 43 CFR 3300: Subpart 3340.3 and appropriate guidelines, enclosed are three copies of as-built Drawing Number 21-12-2020/DI-4A-001, sheets 1 and 2 of 2. Also enclosed are three copies each of the following listed information.

Hydrostatic Test Procedure Hydrostatic Test Pressure and Temperature Charts Hydrostatic Test Data Sheets


After your review, please issue Transcontinental your action of proof of construction accepted.

Yours very truly,

Virgil N. Wallace

Virgil N. Wallace Permit Engineer

VNW:jln Enclosures



PT.	X	Y
RISER A284-"A"	3,648,384.71 '	227, 929 .33 '
I	3,648,275.60'	228,024.76
2	3,648,659.36'	228,738.37
3	3,648,783.21	228,996 .48 '
4	3,648,946.29'	229,385.97
5	3,649,148.24	229,870.71
UWTV	3,649,351.09	230,423 87 '

NOTES:

- Bearings, Coordinates and Distances are based upon the Texas State Plane Coordinate System (Lambert), South Central Zone.
- 2. This pipeline is used to transport natural gas from the Texas O. C. S. to the continental United States.
- 3. As-Built Permanent Right of Way is 200 feet wide.
- 4. The total length of 10" pipeline from the bottom of the riser in Block A-284 to the tie-in assembly at the HIOS U W T V in Block A-283 is 2,784.81 feet or 0.53 miles.

This pipeline was designed and constructed in accordance with the Department of Transportation Regulation, Part 192, Title 49.



181 MANAGER OF CONSTRUCTION

18284

Transcontinental Gas Engineering Department Pipe Line Corporation Houston, Texas A Subsidiary of Transco Companies Inc. AS-BUILT 10" NATURAL GAS PIPELINE IN GULF OF MEXICO AND AREABLK.A-284 TO BLK.A-283 OFFSHORE TEXAS Date 2/17/81 Approved By ROG JKG Checked By TMB Date Date 3-6-81 W O No 5291.37 Scale NONE Sheet 2 of 2 Dwg. No DI-4A-001

SPECIFICATIONS FOR CONSTRUCTION OF OFFSHORE FACILITIES

Page No 34 a

Revision 3/76

ARTICLE 5.00 PIPELINE SPECIFICATIONS (OFFSHORE)

5.10 Testing

Title

5.101 Onshore - This shall include all work and equipment for hydrostatically testing the completed platform piping, riser assemblies, valve assembly(s) and meter station(s) onshore.

The hydrostatic testing shall be performed after the piping has been assembled. Blind flanges and welding caps shall be used to blank openings where required.

Only fesh clean water shall be used for the test. All air shall be evacuated from the piping and displaced with water.

The minimum test pressure will be stated in the Job Description. Pressure shall be determined by a dead weight tester and corrected as necessary for changes in water temperature. Test data shall be recorded on T.G.P.L. Form 1250. The test period shall be for a duration of four (4) hours. Only test data indicating no pressure drop during the test period will be acceptable. If the piping does not meet this test, repairs as necessary shall be made, and the test repeated until an acceptable test is made.

The piping and meter station shall be cleared of all water and purged with air to remove all moisture residue.

5.102 Offshore - This specification covers the testing of the completed pipeline. The pipeline shall be tested using the fluid set out in the Job Description, after completing the cleaning and trenching operations. Contractor may, with the approval of Company, test the pipe in sections or prior to cleaning and trenching. This test, however, shall not be an acceptance test.

The test pressure shall be held on the pipeline for 8 hours after pressure stabilization and shall be checked by means of a standard dead weight gauge, and the data recorded on T.G.P.L. Form 1250. No drop in pressure, after making corrections for changes in temperature and barometric pressure, shall be allowed.

If the pipeline does not meet this test, such steps as necessary shall be taken to cause the pipeline to meet the requirements of the above test.

Approved By

2700 South Post Oak Road P O Box 1396 Houston Texas 77001 SPECIFICATIONS FOR CONSTRUCTION OF

OFFSHORE FACILITIES

Page No 35 a Revision

3/76

ARTICLE 5.00 PIPELINE SPECIFICATIONS (OFFSHORE)

5.102 Offshore (Continued)

Engineering - Pipeline Design

After a hydrostatic test has been accepted, the pipeline shall be freed of water by running as many cylinders or squeegees as deemed necessary, but not less than two. These may be propelled with gas or air. If Company cannot conveniently make gas available Contractor shall furnish air. The Company will handle the gas if it is used for dewatering.

When the platform piping and meter station(s) have been hydrostatically tested independent of the pipeline, the piping shall be drained of all water and thoroughly dried internally by use of compressed air.

Qualification Test Record


								Ref DOT 19	2.501 and 192.
ccount No. N.O- 529	1-27-38	Contract No. (P)			Dara	E \$ 1			
ime Contractor				T	Test Contractor	- 6			
secretion and L	/Y/c	Der mot	ance Being Tested						
0.50	ocalion of Fig	$s \circ F / O$	" Pla Fi	com is	Lock 283	To 13/	KZ	84 HI	
	7 - 1 - 2 - 1								.
		-			DA 7.4				
escription of Pip	De		Length of Test Se	LINE ction From	(M.P. or Blk.) To (N	1.P. or Blk.)	Survey S	Station No.	
D 10.750 W.T		Yld.	0.560 MIL	es BL	KA283 HZ BLK	AJ84HI	From	T	0
D.10.750 w.1			Test Section No.	Eleva	ation of High Point	17:0"	Eleva	tion of Low Point	"
			Drawing Nos. (Ali	gnment or F	abrication)		J		
D. <i>10.750</i> w.	г. <i>0.438</i>	Yld.					T		
D. W.	r .	Yld.	Pipe Manufacturer U.S. S	TEEL			Purch	ase Order No 29	14808 3
	· · · · · · · · · · · · · · · · · · ·			TEST					· · · · · · · · · · · · · · · · · · ·
Туре с		Date Fill	Started Date Fil	I Completed	Water Trea	The state of the s	Avg. Te	mp. Water, Air or	Gas Fill
Gas Air			and Flaustian Who	re Dood Word	Chem	Filter 🗀			
eneral Weather C	Conditions)	lock Location	E	BLK A284 H	T	Elev	vation: +7	10"
nimum Test Pre 2267		d' (High Point)			Maximum Allowable 2681			oint)	
-401	PSI (% of Specif	ied Min. Yield)			· · · · · · · · · · · · · · · · · · ·	% of Spe	ecified Min. Yield	1)
		Source'	TEST W	Location	ID LEAK DATA	\ 	Survey	Sta	M P. or Bloci
III Water		Source		Location			our vey	J.Ca.	The first of Block
est Water Dispos	sal Point	Location'					Survey	Sta	M P. or Block
eak or Test Fail		Location					Survey	Sta.	M P. or Bloc
uring Test									<u> </u>
cidity (_P H) of F	ıll Water	During Fill			•	During Disposal			
	4. F.D. Water	Туре				Quantity			
hemicals Added	to FIII Water								
	T		D WEIGHT PR	ESSURE		TURE LO	3		·
Date of Readings	Time o Reading		sure I.G. An	nbient	Temperature of Ground	Pipe		Ren	narks
30	0220			io rent	a.cu.ng	, , , , ,	- 5	tarted Be	55 U.D
	0300		5 8	315		83°		79 2 7 1 54 7 1 h	
	03 20	ı		31		82			
	03 3	i		31		<u>82</u>			
	03 51			31	-	_82_			
	04 05		1 -	31					
· · · · · · · · · · · · · · · · · · ·	09 21	246		21		<u>82</u>	-		
	0935			00	-	<u> 82</u> 88	<u> </u>	28 3	
	0950	L.		80		- <u>00</u> 82	11/2	福二二	
	0521	266		80		82 82	中户	23 12 12 2 12 2 12 12 12 12 12 12 12 12 12) 'l
	0534			0		82	1	و ما "الاسام	77
	0555			7		82	7.	語是	9
•	0621	266		77		58		HE FE	
·	063:			21		82			
• • • • • • • • • • • • • • • • • • • •	06 50			29		<u>82</u>			m
	0705	1		77		<u>82</u>			
	0720	(1	29		82 82			·
	0750		-	79		<u>- 82</u> 82			
	0805		- · · · · · · · · · · · · · · · · · · ·	27		82			
	08 20			22		92			
	08 35		- /	7 9		82			
	08 50	222	0	2.7		82			
	5005			2	Tank 6 /	<u>82</u>			
eport Prepared	PINA	& Marti	Date	80	Test Supervised By	ral			
esi niiluessea E	V	1) <u>v · </u>	1.1.1.1.1/				
ASI Accepted 5	mored	<u>- (</u>		· · · · · · · · · · · · · · · · · ·	(2) Date		H-	nur -	
	, F	三元	<u></u>		9-5-80			· - ·	
T Test withessed b	inal Copy.	- (S) - (S) Pressure Charts	Tempe	erature Chart	(2) Date 9-5-80 s - Profile	Book Ref.	Hc	our Permits Engr	


Qualification Test Record

BEST AVAILABLE COPY

Ref DOT 192 501 and 192.719

		Contract N	lo. (Prime)		Drece	9		
rime Contractor			0./	L	Test Contract	or		
escription and Lo	cation of Pip	eline or Ap	purtenance Bei	ng Tested				
				1	INE DATA			
escription of Pipe	;		Length		From(M.P. or Blk.)	To (M.P. or Blk.)	Survey Station No.	
.D. WT	·	Yld.	Test Sec	ction No.	Elevation of High F	Point	From Elevation of Low	To Point
D. WT	•	Yld.	Drowns	Nes /Alisamen	it or Fabrication)			
D. W.T	•	Yld.	Drawing	Nos. (Angimer	nt or Fabrication;			
D. W.T		Yld.	Pipe Ma	nufacturer			Purchase Order No	
				Т	EST DATA			
Type of Gas Air	Test Water		Fill Started	Date Fill Com	pleted Wat Chem.	er Treatment Filter	Avg. Temp. Water,	Air or Gas Fill
eneral Weather Co	onditions				nd Weight Readings	Taken [*]		
inimum Test Pres	ssure Specifie		oint)	ation	Maximum Allo	wable Test Pressure	Elevation (Low Point)	
	_ PSI(% of	Specified Min.			PSI (.% of Specified Min.	Yreld)
		Source:			cation	DATA	Survey Sta.	M.P. or Block
ill Water							Survey Sta	M P or Block
est Water Dispos		Location.						
eak or Test Faild uring Test	ıres	Location					Survey Sta.	M P. or Block
cidity (_P H) of Fi	II Water	During Fill				During Disposal		
hemicals Added 1	o Fill Water	Туре				Quantity		
			DEAD WEL	NT DOCCC	UDE AND TEN	IDERATURE I O	^	
Date of	Time o		Pressure	HI PRESS	Temperature	PERATURE LO	G	
Readings	Reading	ıs	P S.I G.	Ambient		Pipe		Remarks
-5-50	09 15		659	5.3		58		
	0930		457 457	82		8 y		
	10 30		656	83		84		
				58				
	11 00		633	-c		89		
	11 00	l l	655 655	82		84		
		2		82 78		84 84		
	11 30 13 00 13 30	2 2	655 655 652	82 78 75		89 84 W 7	8	
	11 30 13 00 13 30 13 00	2 2 2 2	655 652 652	82 78 75 75		84 84 W 7	8	
	11 30 13 00 13 30 1 3 00 13 30	2 2 2 2	455 655 652 652	82 78 75 75 76		89 84 W 7 77 78		
	11 30 13 00 13 30 13 00	2 2 2 2	655 652 652	82 78 75 75		84 84 W 7		eding dame to
	11 30 13 00 13 30 13 30 13 30 14 00	2 2 2 2 2 2 3	652 652 652 652 652	82 78 75 75 76		89 84 W 7 77 78		ending done to
	11 30 13 00 13 30 1 3 00 13 30	2 2 2 2 2 2 2 2	455 655 652 652	81 78 75 75 76 78 78 79		89 84 77 71 78 60 80		ending dame to
	11 30 13 00 13 30 13 30 14 00 14 30 15 00 15 30	2 2 2 2 2 2 2 2 3 1 3 1	655 652 652 652 652 653 503	82 78 75 75 76 78 78 79		89 84 31 7 78 80 80 80 80		ending dame to
	11 30 13 00 13 00 13 30 13 30 14 00 15 00 15 30 16 00	2 2 2 2 2 2 2 2 2 1 1 1 1 1	652 652 652 652 653 653 503 503	82 78 75 75 76 78 78 79		89 84 87 77 78 60 80 80 82 83	Begin ble	
	11 30 13 00 13 30 13 30 14 00 14 30 15 00 15 30	2 2 2 2 2 2 2 2 2 1 1 1 1 1	655 652 652 652 652 653 503	81 78 75 75 76 78 78 79		89 84 31 7 78 80 80 80 80	Begin ble	
	11 30 13 00 13 00 13 30 13 30 14 00 15 00 15 30 16 00	2 2 2 2 2 2 2 2 2 1 1 1 1 1	652 652 652 652 653 653 503 503	82 78 75 75 76 78 78 79		89 84 87 77 78 60 80 80 82 83	Begin ble	
	11 30 13 00 13 00 13 30 13 30 14 00 15 00 15 30 16 00	2 2 2 2 2 2 2 2 2 1 1 1 1 1	652 652 652 652 653 653 503 503	82 78 75 75 76 78 78 79		89 84 87 77 78 60 80 80 82 83	Begin ble	
	11 30 13 00 13 00 13 30 13 30 14 00 15 00 15 30 16 00	2 2 2 2 2 2 2 2 2 1 1 1 1 1	652 652 652 652 653 653 503 503	82 78 75 75 76 78 78 79		89 84 87 77 78 60 80 80 82 83	Begin ble	
	11 30 13 00 13 00 13 30 13 30 14 00 15 00 15 30 16 00	2 2 2 2 2 2 2 2 2 1 1 1 1 1	652 652 652 652 653 653 503 503	82 78 75 75 76 78 78 79		89 84 87 77 78 60 80 80 82 83	Begin ble	
	11 30 13 00 13 00 13 30 13 30 14 00 15 00 15 30 16 00	2 2 2 2 2 2 2 2 2 1 1 1 1 1	652 652 652 652 653 653 503 503	82 78 75 75 76 78 78 79		89 84 87 77 78 60 80 80 82 83	Begin ble	
	11 30 13 00 13 00 13 30 14 00 14 30 15 00 16 00 16 30	2 2 2 2 2 2 2 2 2 1 1 1 1 1 1 1	655 655 652 652 652 653 503 503 503	81 78 75 75 76 78 79 79 79 80 81	7	89 84 77 77 78 80 80 82 83 84	Begin ble	
Report Preparer	11 30 13 00 13 00 13 30 14 00 14 30 15 00 16 00 16 30	2 2 2 2 2 2 2 2 2 1 1 1 1 1 1 1	655 655 652 652 652 653 503 503 503	81 78 75 75 76 78 79 79 79 80 81	Test Suboryis	89 84 77 77 78 80 80 82 83 84	Begin ble	
Report Preparer	11 30 13 00 13 00 13 30 14 00 15 00 15 00 16 00 16 30	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	655 655 652 652 652 653 503 503 503	82 78 75 75 76 78 78 79	Test Supervis	89 84 77 77 78 80 80 82 83 84	Begin ble	accepted by
. /) *	11 30 13 00 13 00 13 30 14 00 15 30 16 00 16 30 16 30	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	655 655 652 652 652 653 503 503 503	81 78 75 75 76 78 79 79 80 81	Test subervis	89 84 77 78 80 80 82 83 84	Begin ble	





BEST AVAILABLE COPY

NOTIFICATION OF CONSTRUCTION

	Date: 7-1-80
1.	OCS Number <u>G-4305</u>
2.	Name of Company Transcontinutal Gass Ripeline Corp.
3.	Name of Contractor Mc Ocenst
4.	Name or Number of Barge #23
5.	Size and Length of Pipeline 10.75 INCh GAS ,55 Miles long
6.	From where to where Transco Exploration Co. "A" platform Took A-284
7.	(area, block number and platform) Where construction begins A' Platform in HLTA -A-284
	(area, block number)
8.	When will barge begin July 9, 1980
9.	How long will barge be on job_30 days
10.	Nearest available heliport on Bonge # 22
11.	Does the pipeline cross or is it in close proximity to fairways or anchorage areas?
	Yes No
	Name of Company Contact Mike Blockwool
	Telephone Number 2/3) 97/-2357
BL	N's Notification to: USGS date N/A U.S. Coast Guard date N/K
-	
Ŋ	IOTE: Notification may be made by calling Autry Britton at A.C. 504 589-6541 between the hours of 7:45 a.m. and 4:15 p.m. Monday through Friday.

A. A.



Transcontinental Gas Pipe Line Corporation

A Subsidiary of Tranceo Companies Inc.

2700 South Post Oak Road P O Box 1398 Houston, Texas 77001 713-871-8000 August 19, 1980
Address Reply To
P.O. Drawer F
Sabine Pass, Texas 77655

U.S. Bureau of Lnad Management Hale Boggs Bldg. 500 Camp St. Suite 841 New Orleans, Louisana 70131

Atten. Mr. Britton,

This letter is written to confirm our telephone conversation on August 19,1980, to advise you that our contractor, J. Ray McDermott proposes to commence hydrostatic testing on permit OCS-G-4315 on/about 8-21-80 and permit OCS-G-4305 on/about 8-27-80.

The Venners

asotruly,

J.B. Coward Chief Inspector

Transcontinental Gas Pipe Line Corp.

IBC/mgb

cc: M.J. Hunter

Paul Newton

File

BEST AVAILABLE COPY

SECTIVED SELVED SUR OF THE PROPERTY OF THE PRO

FALL WILL STATE OF THE PARTY OF

ATTACHMENT 5

NOTIFICATION OF HYDROSTATIC TEST

Date: 8-19-80
OCS Number <u>4305</u>
Name of Company TRANSCONTINEAST a 1 GAS P/L CORP.
Size of Pipeline 10" GAS Length Miles 155
From where to where Transco Exploration Co's "A" Platform in BL A-28 (area, block number and platform name) Co Sulsea tie with OCS-G 3302 in Brock A-283
all - High ISLAND Area.
Platform where hydrostatic test instruments will be set up <u>A'Platform</u> — 13 lock A-384 H. I.A.
Contractors Name and Barge Name or Number Mc Dermott
Date and Time of Proposed Test . 8-27-80
Name of Company Contact Mike Blackwood Telephone Number (2/3) 971-2357 BLM's Notification To: USGS WA U. S. Coast Guard W/A

NOTE: Notification may be made by calling Autry Britton at A.C. 504 589-6541 between the hours of 7:45 a.m. and 4:15 p.m. Monday through Friday.

A. AAAA



A Subsidiary of Transco Companies Inc.

2700 South Post Oak Road P O Box 1396 Houston, Texas 77001 713-871-8000 July 7, 1980 Address Reply To

P.O. Drawer F Sabine Pass, Texas 77655

U.S. Bureau of Land Management Hale Boggs Building 500 Camp St. Suite 841 New Orleans, La. 70131

Atten. Mr. Britton

This letter is written to confirm our telephone conversation on July 7, 1980, to advise you that our contractor, J. Ray McDermott, proposes to commence work on the following permits, OCS-G-4305, OCS-G-4019 and OCS-G-4315, on/about July, 9, 1980. This work will be done by the lay barge #22, which is equipped with a heliport.

It is estimated that this work will take approximately 90 days to complete.

Chief Inspector

Transcontinental Gas Pipe Line Corp.

IBC/mgb

cc: M.J. Hunter
Paul Newton
File

JUL 14 1 113 PH '80
JUL 14 1 113 PH '80
BUR O' CONTRACTOR CONTRACT

MEM QUIEN	ns Ges
THE GIVE	- ord-free
上的一位	CALLY .
- Wen	_
ASST, WE	W CARRETTE
JUL 14	1980
P. LEGAL	
PAD	
EAD	d
OPS	
STUDIES	
RONL S	

5N5842 N

OCS-G 4305

BEST AVAILABLE COPY

High Island Area, East Addition, South Extension

May 14, 1980

Transcontinental Gas Pipe Line Corporation

Right-of-Way

ACTION: APPLICATION APPROVED

Your application for a right-of-way 200 feet in width for the construction, maintenance, and operation of a ten (10) inch natural gas pipeline, 0.55 miles in length, from Transco Exploration Company's Platform "A" in Block A-284, to a subsea tie-in with the High Island Offshore System 30-inch pipeline (OCS-G 3302) in Block A-283, all located in High Island Area, East Addition, South Extension, dated March 10, 1980, with its attachments is hereby approved with the following addition and correction:

1. Buoy the existing HIOS 30-inch pipeline to prevent possible damage during construction of the proposed 10-inch pipeline.

John L. Rankin Manager

cc: Geological Survey, USDI Office of Pipeline Safety Operations, USDT

Scheners 4/25/80 Stenll 4/28/80 Solana 4/29/80 Mark 30

In Reply Refer To OS-5

MAY 1 1980

Memorandum

To:

Manager, Bureau of Land Management, 841 Hale Boggs Federal Building,

500 Camp Street. New Orleans, Louisiana 70130

From:

Conservation Manager, Gulf of Mexico OCS Region

Subject:

Transcontinental Gas Pipe Line Corporation's Pipeline Application,

BLM OCS-G 4305

We have reviewed the safety features and design specifications for the subject Right-of-Way Application, dated March 10, 1980, in accordance with the MOU dated August 1, 1974. It is for the construction, maintenance and operation of a 10 3/4-inch natural gas and gas condensate pipeline 2,896 feet in length from Transcontinental Exploration Company's Platform A, High Island Block A-284, Lease OCS-G 3951, to a subsea tie-in with a 30-inch HIOS pipeline in High Island Block A-283, Lease OCS-G 2404-

Based upon information submitted in the application, the design characteristics of this pipeline are calculated to be as follows:

Pi	pel	ine	Component	

Maximum Allowable Operating
Pressure/WP Ratings

Submerged	component
Riser comp	onent
Valves, fl	anges, fittings

2,053 psig 1.628 psig 1,440 psig

The hydrostatic pressure test with water will be in the range of 2.624 to 2,681 psig for eight hours for the submerged component. The riser will be preinstallation-tested to a pressure in the range of 2,995 to 3,060 psig for four hours. The ANSI 600 valves should not be subjected to a test-pressure differential greater than 1,440 psig. The ANSI 600 valves, flanges, and fittings should not be subjected to a body test greater than 2,175 psig.

Based on these calculations and a maximum allowable operating pressure (MAOP) of 1,440 psig of the receiving 30-inch HIOS pipeline (BLM OCS-G 4305), we recommend that the MAOP for this pipeline be 1,440 psig, and that this pressure may be exceeded only when hydrostatically pressure-testing the pipeline. We also recommend that valves and taps at the subsea tie-in be provided with a minimum of three feet of cover, either through burial or with sandbags.

2

Our records indicate there are two existing pipelines within 4.000 feet of the subject pipeline. We recommend that the applicant be advised of the presence of these lines so that they can be avoided in the planning and conduct of his operations.

The technical aspects of the proposed pipeline are acceptable in accordance with appropriate regulations and standards.

We would appreciate receiving a copy of the plat showing the location of the pipeline as installed.

(Orig. Spil.) - J. Courtouy Book

FOR Lowell G. Hammons

cc: 1502-01 BLM OCS-G 4305 (w/orig appln) (OS-5)
CM Reading File
OMS-4 (w/cy of location plat)

GHSchonekas:nnk:4/25/80



United States Department of the Interior

GEOLOGICAL SURVEY

IMPERIAL OFFICE BLDG . 3301 N CAUSEWAY BLVD

NEW ORLEANS OGS 7944

TEL	(504)	837-4720	

FILE CORRIE LOUISIANA 70010

In Reply Refer To: OS-5

ROUTE INITIAL MGR. ASST. MGR.

MAY 1 1980 .

Mandania Allanakla Asamatina

MAY 0 2 1980 P. LEGAL —

Memorandum

Manager, Bureau of Issupies

Manager, Bureau of lamudicanagement, 841 Hale Boggs Federal Building,

500 Camp Street, New MGM Teams, Louisiana 70130

From:

To:

Conservation Manager, Gulf of Mexico OCS Region

Subject:

Transcontinental Gas Pipe Line Corporation's Pipeline Application,

BLM OCS-G 4305

We have reviewed the safety features and design specifications for the subject Right-of-Way Application, dated March 10, 1980, in accordance with the MOU dated August 1, 1974. It is for the construction, maintenance and operation of a 10 3/4-inch natural gas and gas condensate pipeline 2,896 feet in length from Transcontinental Exploration Company's Platform A, High Island Block A-284, Lease OCS-G 3951, to a subsea tie-in with a 30-inch HIOS pipeline in High Island Block A-283, Lease OCS-G 2404.

Based upon information submitted in the application, the design characteristics of this pipeline are calculated to be as follows:

Pipeline Component	Pressure/WP Ratings
Submerged component	2,053 psig
Riser component	1,628 psig
Valves, flanges, fittings	1,440 psig

The hydrostatic pressure test with water will be in the range of 2,624 to 2,681 psig for eight hours for the submerged component. The riser will be preinstallation-tested to a pressure in the range of 2,995 to 3,060 psig for four hours. The ANSI 600 valves should not be subjected to a test-pressure differential greater than 1,440 psig. The ANSI 600 valves, flanges, and fittings should not be subjected to a body test greater than 2,175 psig.

Based on these calculations and a maximum allowable operating pressure (MAOP) of 1,440 psig of the receiving 30-inch HIOS pipeline (BLM OCS-G 4305), we recommend that the MAOP for this pipeline be 1,440 psig, and that this pressure may be exceeded only when hydrostatically pressure-testing the pipeline. We also recommend that valves and taps at the subsea tie-in be provided with a minimum of three feet of cover, either through burial or with sandbags.

0/03.

<u>.</u>

Our records indicate there are two existing pipelines within 4,000 feet of the subject pipeline. We recommend that the applicant be advised of the presence of these lines so that they can be avoided in the planning and conduct of his operations.

The technical aspects of the proposed pipeline are acceptable in accordance with appropriate regulations and standards.

We would appreciate receiving a copy of the plat showing the location of the pipeline as installed.

Courtny Resp Lowell G. Hammons



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

0CS-G 4305 - O

NEW ORLEANS OUTER CONTINENTAL SHELF OFFICE
HALE BOGGS FEDERAL BUILDING
500 CAMP STREET-SUITE 841
NEW ORLEANS, LA 70130

April 3, 1980

Memorandum

To:

Conservation Manager

Gulf of Mexico OCS Operations

From:

Manager

New Orleans OCS Office

Subject: Review of Pipeline Right-of-way Application (OCS-G 4305)

In accordance with the memorandum of understanding between the Bureau of Land Management and U. S. Geological Survey signed August 1, 1974, the subject application is enclosed.

Please review the technical aspects of the proposed pipeline. If you have any questions regarding this matter, please contact Mr. Autry J. Britton of this office.

NOTED-SCHONEKAS APR 4 1980

Enclosures

1-Application dated March 10, 1980

2-Engineering Data, undated

3-Drawing No. 21-2020/DI-A-001, Sheets 1 thru 4 of 4

4-Drawing No. 21-2022/DI-A-002, Sheet 1 of 1



4

A Subsidiary of Transco Companies Inc.

2700 South Post Oak Road P. O. Box 1396 Houston, Texas 77001 713-871-8000

March 10, 1980

Mr. John L. Rankin, Manager New Orleans OCS Office Bureau of Land Management Hale Boggs Federal Building 500 Camp Street, Suite 841 New Orleans, Louisiana 70130

Re: Application for right of way for proposed 10" pipeline Block A-283 to A-284 High Island Area, Offshore Texas, Gulf of Mexico Line No. 1-1014, R/W 1

Dear Mr. Rankin:

Pursuant to the authority granted in Section 5(e) of the Outer Continental Shelf Lands Act (67 Stat. 462), (43 U.S.C. 1331), as amended (92 Stat. 629), and in compliance with the regulations contained in Title 43 CFR 3340, Transcontinental Gas Pipe Line Corporation hereby applies, in triplicate, for a right-of-way two hundred feet (200 ft.) in width to construct, maintain and operate a 10" natural gas pipeline as shown on the following drawings.

Block Survey Report

Vicinity, Route, Profile and Cathodic Protection Drawing, Drawing Number 21-2020/DI-A-001

Schematic Drawing Drawing Number 21-2022/DI-A-002

The 10" pipeline will be used to transport natural gas and condensate from the proposed Transco Exploration platform "A" located in Block A-284 to an existing underwater valve assembly on the 30" HIOS pipeline in Block A-283 all in the High Island Area, East Addition, South Extension, Gulf of Mexico.

In accordance with applicable regulations, the applicant agrees it will mail to each lessee or right-of-way holder whose lease or right-of-way is affected by this application, by registered mail, return receipt requested, a copy of the application and the maps attached hereto. A list of such lessees and right-of-way holders is attached and copies of the return receipts showing service upon such lessees and right-of-way holders will be forwarded to your office when received.

HEREN 12 27 PH 18
BUR OF LAND HEAT.
OUTER TO THE STALL
SHEET TO HERE

Bureau of Land Management LAND/905103 March 10, 1980 Page 2

As set forth in the February 13, 1978 guidelines, and as amended the applicant agrees to the following:

- 1. The pipeline will be buried a minimum of three (3) feet below the mud line because the water depths do not exceed two hundred (200) feet.
- 2. The proposed pipeline will cross no existing pipeline.
- 3. All valves and fittings on the submerged pipeline will be buried to a minimum of one (1) foot below the mud line.
- 4. Sensing devices and fail close valves will be installed as shown on the enclosed Schematic Drawing 21-2022/DI-A-002.
- 5. Two (2) copies of a Block Survey Report prepared for Transco are enclosed.
- 6. All changes, additions or deletions to any equipment on the pipeline will be made only after first securing the expressed written approval of your office.
- 7. Your office will be notified at least five (5) days prior to commencing construction and will be advised of construction date, approximate starting time, starting point, name of contractor and barge, availability of heliport facilities and approximate completion date.
- 8. Your office will be notified forty eight (48) hours in advance of the hydrostatic test and will be advised of the location of the pressure recorder and approximate starting time of the test. Hydrostatic test data, including procedure, hold time and results will be furnished to your office within ninety (90) days following the test.
- 9. Within ninety (90) days after completion of construction, applicant will provide an as-built map establishing the location of the completed pipeline within an accuracy of +/- 100 feet, prepared in accordance with the requirements for the map depicting the proposed route reflecting the total length of the line (all in feet) and depicting those points, if any, at which the pipeline is located outside of the right of way.
- 10. Any break, leak, failure or accident will be reported within twelve (12) hours after such occurrence as provided for in said guidelines.
- 11. This application (and any amendments made hereto) is made with our full knowledge and concurrence with the OCS Lands Act (43 U.S.C. 1331 et seq.), as amended (P.L. 95-372), including the following: Sec. 5(e) addressing pipeline rights-of-way, Requirements of the Federal Energy Regulatory Commission notice of hearing, transportation and purchase of oil and gas without discrimination; Sec. 5(f)(1) addressing operation of pipelines in accordance with competitive principles, including open and nondiscriminatory access to both owner and non-owner shippers; Sec. 5(f)(2) which may allow exemption of the

Bureau of Land Management LAND/905103 March 10, 1980 Page 3

requirements in Sec. 5(f)(1); and Sec. 21(b), addressing the assuring of maximum environmental protection, including the safest practices for pipeline burial.

Additionally, we expressly agree that if any site, structure, or object of historical or archaeological significance should be discovered during the conduct of any operations within the permitted right-of-way, we shall report immediately such findings to the Manager, New Orleans OCS Office, and make every reasonable effort to preserve and protect the cultural resource from damage until the Manager, New Orleans OCS Office, has given directions as to its preservation.

Additional design criteria data is as follows:

- 1. The length of the 10" pipeline between the riser and the proposed underwater tap valve is 2,896 feet or 0.55 miles.
- 2. The line pipe will be:

```
10.750" O.D. x .365" W.T., API 5LX Gr. x-42, 40.48 lbs/ft.
10.750" O.D. x .438" W.T., API 5LX Gr. x-42, 48.19 lbs/ft.
10.750" O.D. x .500" W.T., ASTM A-106 Gr. B, 54.74 lbs/ft.

3. The riser piping at the platforms will be:
```

10.750" O.D. x .500" W.T., ASTM A-106 Gr. B, 54.74 lbs/ft.

- 5. The water depth is approximately 183 feet in Blocks A-283 and A-284, High Island Area, East Addition, South Extension.
- 6. The cathodic protection system will be Galvalum III bracelet anodes, as described on Dwg. 21-2020/DI-A-001, Sheet 4 of 4.
- 7. The products to be transported are natural gas and condensate, neither of which is corrosive to carbon steel pipe interior. However, the analysis of the transported product will be monitored and preventive measures such as pigging and/or inhibiting will be employed as necessary.
- 8. Protective coatings used on the underwater line pipe are:

```
10" x .365" W.T., 1" thick - 140 PCF concrete, 1/2" mastic 10" x .438" W.T., 1" thick - 140 PCF concrete, 1/2" mastic 10" x .500" W.T., 1" thick - 140 PCF concrete, 1/2" mastic
```

9. The bulk specific gravity of the empty pipe in seawater is:

Pipe Size	Specific Gravity
10.750" x .365"	1.45
10.750" x .438"	1 . 57
10.750" x .500"	1.67

- 10. The anticipated specific gravity of the natural gas is 0.60 and the condensate is 0.75.
- 11. The design working pressure of the pipeline is as follows:

Maximum Allowable Operating Pressure based on valves and flanges will be 1,440 psig (maximum working pressure of ANSI 600# valves and flanges).

Maximum Allowable Operating Pressure based on line pipe will be:

$$MAOP = \underbrace{2 St}_{D} \times F \times E \times T$$

MAOP =
$$\frac{2(35,000) \times .365}{10.750}$$
 x .72 x 1.0 x 1.0 = 2,053

MAOP =
$$\frac{2(42,000) \times .438}{10.750}$$
 x .72 x 1.0 x 1.0 - 2,464

MAOP =
$$\frac{2(35,000) \times .500}{10.750}$$
 x .72 x 1.0 x 1.0 x = 2,344 psig

Maximum Allowable Operating Pressure based on the riser piping will be:

MAOP =
$$\frac{2(35,000) \times .500}{10.750}$$
 x 0.5 x 1.0 x 1.0 = 1,628 psig

Therefore, the Maximum Allowable Operating Pressure of the system is limited to a maximum allowable pressure of 1,440 psig, based on valves and flange ratings.

- 12. The anticipated operating pressures are estimated to range from 750 psig to 1,200 psig.
- 13. The design capacity of the line is 30 MMCFD based on an inlet pressure of 1,002 psig and an outlet pressure of 1,000 psig.

Bureau of Land Management LAND/905103 March 10, 1980 Page 5

14. The pipeline will be hydrostatically tested to a minimum pressure of 2,624 psig not exceeding a maximum pressure of 2,681 psig and held for 8 hours. The riser piping will be hydrostatically tested to a minimum pressure of 2,995 psig not exceeding a maximum pressure of 3,060 psig and held for 4 hours.

The ANSI 600# and 900# valves, flanges and fittings will not be subjected to a body test pressure greater that 2,175 and 3,250 psig, respectively.

- 15. The design pipe depth is shown on Drawing No. 21-2020/DI-A-001, Sheet 2 of 4 sheets.
- 16. The platform risers below water will be coated with 3 mils (dry) of inorganic zinc-rich primer and then flake glass filled epoxy phenolic for a total dry film thickness of 24 to 40 mils.

The piping above-water will be coated with 3 mils (dry) inorganic zinc-rich primer and then Hi-Build catalyzed epoxy for a total dry film thickness of 15 mils.

- 17. All piping, fittings, risers and components of the pipeline are designed in compliance with 49 CFR 192.
- 18. Construction information:

Estimated Starting Date
Method of Construction
Method of Burial
Estimated time required to lay and bury pipe
Estimated time to complete project

July 1, 1980 Lay Barge Jet Bury Barge 2 weeks 4 weeks

19. Company Contact:
Paul E. Newton, Supervising Engineer, Permits
Transcontinental Gas Pipe Line Corporation
P. O. Box 1396
Houston, Texas 77001
Telephone (713) 871-2533

Enclosed are three copies each of the maps and drawings referred to above, prepared and certified in accordance with applicable guidelines. Also enclosed is an engineering data attachment of three pages.

A certified copy of the articles of incorporation and certificate of the Assistant Secretary, under seal, certifying that the corporate officer executing the application has the authority to do so have already been submitted to your office. These documents have been placed on record in a file identified as New Orleans Miscellaneous File No. 011. A filing fee of \$100.00, together with the first year's rental of \$15.00 computed on 0.55 miles of right-of-way, is enclosed.

Bureau of Land Management LAND/905103 March 10, 1980 Page 6

Also enclosed please find a Nondiscrimination in Employment statement executed by a Vice President of Transcontinental Gas Pipe Line Corporation.

If the above and attached information meets with your approval, we would appreciate your issuing the necessary right-of-way at your earliest convenience. Inquiries concerning this application may be directed to the applicant at P. O. Box 1396, Houston, Texas 77001.

Very truly yours,

TRANSCONTINENTAL GAS PIPE LINE CORPORATION

Vice President What has

Enclosures

HAR 13 12 27 PM *81
BUR OF LAND MANTAL
OUTER CONTINENTAL

LESSEES AND RIGHT-OF-WAY HOLDERS

HIGH ISLAND AREA, EAST ADDITION, SOUTH EXTENSION

Oil & Gas Block A-283

KOCH Industries, Inc. OCS-G 2404 General American Oil Company

of Texas

TransOcean Oil, Inc. Gulf Oil Corporation Unidel Oil Corporation

Pipeline

OCS-G 3302 High Island Offshore System

Oil & Gas Block A-284

OCS-G 3951 Transco Exploration Company

Energy Development Corporation

Pipeline

OCS-G 3302 High Island Offshore System



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

NONDISCRIMINATION IN EMPLOYMENT

As a condition precedent to the approval of the granting of the subject pipeline right-of-way, the grantee <u>Transcontinental Gas Pipe Line Corporation</u> hereby agrees and consents to the following stipulation which is to be incorporated into the application for said right-of-way.

During the performance of this grant the grantee agrees as follows:

During the performance under this grant, the grantee shall fully comply with paragraphs (1) through (7) of section 202 of Executive Order 11246, as amended, (reprinted in 41 CFR 60-1.4 (a)), which are for the purpose of preventing discrimination against persons on the basis of race, color, religion, sex or national origin. Paragraphs (1) through (7) of section 202 of Executive Order 11246, as amended, are incorporated in this grant by reference.

Transcontinental Gas Pipe Line Corporation

Signature of Grantee

Vice President

Date: March 10, 1980

HAR 13 12 28 PM 80

BUR OF LAND KOMTAL

BUR OF

ENGINEERING DATA HIGH ISLAND AREA BLOCK A-284, 10" PIPELINE

- 1. The pipeline will be buried to a minimum depth of 3 feet since the water depth does not exceed 200 feet at any point.
- 2. The proposed pipeline will cross no existing pipelines.
- 3. All values and fittings on the submerged component will be buried to a minimum of one foot below the mudline.
- 4. The length of the line between the riser and proposed underwater tap valve is 2,896 feet or 0.55 mile.
- 5. The line pipe will be:

10.750" O.D. x .365" W.T., API 5LX Gr. x-42, 40.48 lbs/ft.

10.750" O.D. x .438" W.T., API 5LX Gr. x-42, 48.19 lbs/ft.

ម s/ft. ១ מונים

10.750" O.D. x .500" W.T., ASTM A-106 Gr. B, 54,74 lbs/ft.

6. The riser piping at the platform will be:

10.750" O.D. x .500" W.T., ASTM A-106 Gr. B, 54.74 lbs/ft.

B PH 38 PH 3

- 7. The water depth is about 183 feet throughout the length of the pipe in Blocks A-283 and A-284 High Island Area.
- 8. The cathodic protection system will be Galvalum III bracelet anodes, as described on Drawing 21-2020/DI-A-001, Sheet 4 of 4.
- 9. The products to be transported by the pipeline are natural gas and condensate, neither of which is corrosive to carbon steel pipe interior. However, the analysis of the transported product will be monitored and preventive measures such as pigging and/or inhibiting will be employed as necessary.
- 10. Protective coatings used on the underwater line pipe are:

10" x .365" W.T., 1" - 140 PCF concrete; 1/2" mastic

10" x .438" W.T., 1" - 140 PCF concrete, 1/2" mastic

10" x .500" W.T., 1" - 140 PCF concrete, 1/2" mastic

11. The bulk specific gravity of the empty pipe in seawater is:

PIPE SIZE	S.G.
10.750" x .365"	1.45
10.750" x .438"	1.57
10.750" x .500"	1.67

- 12. The anticipated specific gravity of the natural gas is 0.60 and the condensate is 0.75.
- 13. The design working pressure of the system is as follows:

Maximum Allowable Operating Pressure based on valves and flanges will be '1440 psig (maximum working pressure of ANSI 600 valves and flanges).

Maximum Allowable Operation Pressure based on line pipe will be:

$$MAOP = \underbrace{2 \text{ St}}_{D} \times F \times E \times T$$

MAOP =
$$\frac{2(42,000) \times .365}{10.750} \times .72 \times 1.0 \times 1.0 = \frac{2053}{10.750}$$
 psig

MAOP =
$$\frac{2(42,000) \times .438}{10.750} \times .72 \times 1.0 \times 1.0 = \frac{2464}{10.750}$$
 psig

MAOP =
$$\underline{2(35,000)} \times .500 \times .72 \times 1.0 \times 1.0 = \underline{2344}$$
 psig



Maximum Allowable Operating Pressure based on the riser piping will be-

MAOP =
$$\frac{2(35,000) \times .500}{10.750} \times 0.5 \times 1.0 \times 1.0 = \frac{1628}{10.750}$$
 psig

Therefore, the Maximum Allowable Operating Pressure of the pipeline is $\underline{1440}$ psig based on the valves and flanges.

- 14. The anticipated operating pressures are estimated to range from 750 psig to 1200 psig.
- 15. The design capacity of the line is 30 MMCFD based on inlet pressure of 1002 psig and outlet pressure of 1000 psig.
- 16. The hydrostatic test pressure and hold time for the pipeline will be 2624 to 2681 psig for 8 hours. The riser will be hydrostatically tested at 2995 to 3060 psig for 4 hours.

The ANSI 600 and 900 valves, flanges and fittings will not be subjected to a body test greater than 2175 and 3250 psig, respectively.

- 17. The design burial depth is shown on Drawing 21-2020/DI-A-001, Sheet 2 of 4.
- 18. The platform riser below water will be coated with 3 mils (dry) of inorganic zinc-rich primer, and then flake glass-filled epoxy phenolic for a total dry film thickness of 24 and 40 mils.

The above water piping will be coated with 3 mils (dry) of inorganic zinc - rich primer and then Hi-Build catalyzed epoxy for a total dry film thickness of 15 mils.

- 19. All piping, fittings, riser and components of the pipeline are designed in compliance with 49 CFR 192.
- 20. Construction information:

A. Estimated Starting Date:

B. Method of Construction:

July 1, 1980

Lay Barge

C. Method of Burial: Jet Bury Barge


D. Estimated Time Required to Lay and Bury Pipe: 2 weeks


E. Estimated Time to Complete Project: 4 weeks

21. Company Contact:

Paul E. Newton, Supervising Engineer, Permits Transcontinental Gas Pipe Line Corporation P.O. Box 1396 Houston, Texas 77001 Telephone (713)871-2533

HAR 13 12 29 PN 80BUR OF LAND MENTAL
OUTER CONTINENTAL
NEW ORI STARS. LA.





Proposed 10" Pipeline From TXC Platform "A" To HIOS Tap Valve

Pt.	Bearing	Distance	Remarks	x	Y	Lat.	Long.
_1			Bottom of Riser Platform "A"	3,648,364 29	227,930 82	28° 21' 38.943"	93° 52′ 24.310″
1 - 2	N 85° 00' 00.0" W	150.00′	P.I	3,648,214.86	227,943.89	28° 21′ 39 137″	93° 52' 25.975"
2 - 3	N 24° 59′ 22.7″ E	2,746.20	HIOS Tap Valve	3,649,375 00	230,433.00	28° 22' 03.256"	93° 52′ 11.780′′

Total Length 2,896 20 Feet or 0.55 Miles

BUR OF I AND HOMT.
OUTER CONTINENTAL
SHELL OFFICE
SHELL OFFICE

NOTES:

- 1. THE PIPELINE WILL BE USED TO TRANSPORT NATURAL GAS FROM THE TEXAS O.C.S. TO THE CONTINENTAL UNITED STATES.
- 2. COORDINATES, BEARINGS, AND DISTANCES SHOWN ARE BASED ON TEXAS (LAMBERT) PLANE COORDINATE SYSTEM, SOUTH, CENTRAL ZONE
- 3: VERTICAL DATUM: LOCAL GULF LEVEL AT TIME OF SURVEY
- 4. BOTTOM OF GULF PROFILE TAKEN FROM HAZARD SURVEY CHARTS.
- 5. PROPOSED PERMANENT R.O.W. 200 FEET IN WIDTH.

I hereby certify that the design of the Pipeline complies with Department of transportation Regulation Part 192,

Title 49,

RUSSELL J. JUDAH


18284


SIGNAL

Date Number

065-6 N309 Transcontinental Gas Engineering Department Pipe Line Corporation Houston Texas A Subsidiary of Transco Companies Inc. PROPOSED NATURAL GAS PIPELINE IN THE GULF OF MEXICO HIGH ISLAND AREA BLK. A-283 TO A-284 OFFSHORE, TEXAS Drawn By SW Q D Date | 30 80 Approved By ROG Date 2-4-80 Checked By Da Scale Noted 21-2020 Dwg. No. DI Sheet 3 of 4

PROPOSED 10" PIPELINE FROM PLATFORM "A" TO HIOS TAP VALVE - BLK. A-283





Weight: 64 Lbs.

Scale: N.T.S

NOTES:

1. Galvalum III Anodes Theoretical Rating = 0.1530 Amp. Year Lbs.

Practical = 0.1530 x 75% Effective x 85% use factor = 0.0975 Amp. Year Lbs.

2. Assuming 2% Damaged Coating and .005 Amperes Per Square Foot Required for Protection.

Current Required = CR

CR = Total Area x 0.02 x 0.005

 $= 8150.9 \text{ Sq. Ft.} \times 0.0001$

CR = 0.82 Amperes

3. Pounds of Galvalum III Required for 40 Years Protection:

Lbs. = (0.82 Amperes/0.0975 Amp. Year) x 40 Years

Lbs. = 334.40

4. 11.00" I.D. Galvalum III Anodes: 64 Lbs. Each.

Number of Anodes Required = N.R.

N.R. = 334.40 / 64

N.R. = 5.22

- 5. 6-11.00" I.D. Galvalum III Anodes, On 480 Foot Spacing Will Be Installed. The First Anode On The Pipeline Will Be 100 Feet From Platform "A". There Will Be 2 Anodes Placed At The Base Of The Riser Assembly and 1 Anode Placed on U/W Tap Valve Assembly.
- 6. Pipeline To Environment Voltages Will Be Observed At The Platform After The Line Is In Place To Assure That Adequate Corrosion Protection Is Being Provided.
- 7. Total Number Anodes Required = 9.

Inereby certify that the design of the Pipeline complies with Department of transportation Regulation Part 192. Title 49

Number

OFFSHORE, TEXAS Date 1-31-80 Drawn By SWGN Approved By RoG Checked By Dat 2 -1-80 Date 2 -1-80

15-6 430G

Transcontinental Gas Engineering Department Pipe Line Corporation Houston, Texas


A Subsidiary of Transco Companies Inc.

Dwg. No.

PROPOSED NATURAL GAS PIPELINE IN THE GULF OF MEXICO

HIGH ISLAND AREA BLK. A-283 TO A-284

Date 2-4-80 (Michalm) W. O. No. 5291.37 _{Scale} None 21-2020 DI-A-001 Sheet 4 of 4



PRODUCER'S COALESCER 1440 DESIGN PRESSURE

TXC PLATFORM "A" BLOCK A-284 HIGH ISLAND AREA

LENGTH

PIPE

1,295' 10.750" O.D. x .500" W.T.; A.P.T.M. A106 Gr. B 400' 10.750" Q.D. x .438" W.T., A.P.I. 5LX Gr. X-42 1,201 10.750" Q.D. x .365" W.T., A.P.I. 5LX Gr. X-42 2,496

Connection To Producer's Automatic & Remote ESD System

NOTES:

- 1 System MAOP = 1440 p.s.ig.
- 2. ALL Underwater Valves are ANSI 900
- 3 Pipeline is Cathodically protected with Sacrificial Anodes
- 4 ALL Platform Valves are ANSI 600

I hereby certify that the design of the Pipeline complies with Department of Transportion Regulation Part 192, Title 49,



2-25-80 EI

ENGINEER 900/

NUMBER

HIGH A- 283

005-6.4305

Transcontinental Gas Engineering Department Pipe Line Corporation Houston, Texas

A Subsidiary of Transco Companies Inc

SCHEMATIC FLOW DIAGRAM

PROPOSED IO" PIPELINE FROM BLOCK A-284

TO BLOCK A-283 HIGH ISLAND AREA

OFFSHORE TEXAS

Checked By S Date 7-14-80 Approved By PULL Date 2-25-80

Checked By S Date 7-14-80 Approved By Dute Engineer

W. O. No. 5291. 37 Scale None General Group

Sheet I of I Dwg. No. DI- A-002

ocs-6 <u>430</u>5

"ENGINEERING CHECK LIST"

ENGINEER WILL VERIFY THE FOLLOWING:

<i></i>	
A.	The safety schematic is complete and depicts adequate engineering design.
<u></u> <u> </u>	The design information submitted in the application or on the dat sheet is complete and acceptable.
<u>c</u> .	The pipeline is buried in areas requiring burial.
N/AD.	All pipeline crossings are designed properly and buried in areas requiring burial.
F.	The application is forwarded to the U. S. Geological Survey.
<u>/</u> F.	Geological Survey completes technical review.
G.	Geological Survey's technical review agrees with engineering review.

"I have reviewed the proposed pipeline right-of-way application and have verified that it is designed in compliance with federal regulations. It meets the minimum standards of safety as established by the Department of Transportation and the Department of the Interior."

Signature of Engineer)

0

PIPELINE RIGHT-OF-WAY APPLICATION "ENGINEERING CHECK LIST" Bureau of Land Management New Orleans OCS Office

Date: 3 - 17 - 80OCS-G 43.05

Α.	Description of pipeline and location of proposed route (i.e., size of pipe; product to be transported; from where to where; platform number; name; block number; area and distance in feet and miles): for a 10.75 inch Makual 6 and Condensate pipeline from Musico Exploration Company "A" Platform in Block A-284 to subser the with HTOS 30" Pipeline in Block A-283 allocated in High Island area Earl Rod, S. Exti for a total length of 3,784.81" is 53 miles.
В.	Safety Flow Schematic - Verify that the information shown on the safety flow schematic diagram contains the following:
	1. Pressure source is drawn into the schematic with the following: a. source (i.e., name) Coalescer & Glycollastoctor
	b. design working pressure 1440 Psig
	c. hi-lo pressure sensor settings 1440 psig
	2. "ANSI" ratings of all valves, flanges and fittings between the source and the connecting pipeline are shown.
	3. Pressure relief valves, where applicable, are shown with the setting set no higher than the maximum allowable working pressure (MAWP) of the vessel.
	If the maximum input source pressure is greater than the maximum allowable operating pressure (MAOP) of the pipeline, redundant safety equipment is required.
	5. MAOP of proposed pipeline does not exceed MAOP of connecting pipeline.
	The pipeline leaving the platform receiving production from the platform is equipped with high-low pressure sensors to directly or indirectly shut-in the well or wells on the platform.
	The pipeline delivering production to the production facilities on the platform is equipped with an automatic fail-close valve tied into the automatic and remote shut-in system.

8.	The pipeline crossing the platform which does not deliver production to the platform, but which may or may not receive production from the platform, is equipped with high and low pressure sensors connected to an automatic fail-close valve located in the upstream portion of the pipeline at the platform. In addition, the sensors are tied into either the platform's automatic and remote shut-in system or an independent remote shut-in system.
19.	The pipeline boarding the platform/pipeline is equipped with a check valve.
10.	The pipeline leaving the platform is equipped with a check valve.
<u></u>	The high-low pressure sensors on departing pipeline located upstream of the check valve.
<u>∠</u> 12.	Where applicable, high-low sensors located downstream of the back pressure regulator.
<u>L</u> 13.	If there is liquid injection into the line, are pumps associated with the injection? (Yes or no)
CY4.	Direction of flow indicated.
	Pipe specifications (i.e., size, grade, weight and wall thickness).
	Total length of proposed pipeline (feet and miles).
47.	MAOP of connecting pipeline. OCS-G 3302) 1440 PSig.
	Statement that design meets or exceeds DOT Regulations 192 or 195, as applicable, registered engineer's seal, registration number, date and signature.
19.	Area and block number of proposed pipeline/platform.
<u>L20.</u>	Cathodic protection specifications.
Design applica	Information - Verify that the pipeline design information given in the tion and/or on the data sheet is complete and correct:
41.	Product to be transported: Natural Gas and Condensate
12.	Pipeline, riser and subsea valve assembly specifications:
	a. Pipeline:
	(1) Size 10.75" Wall Thickness 365 Grade 1-42 Weight 40.48 Mafft
	(1) Size 10.75" Wall Thickness 365 Grade 1-42 Weight 40.48 Mafft. (2) Size 10.75" Wall Thickness 438 Grade 1-42 Weight 48.19 Mafft.
	(3) Size 10.75 Wall Thickness . 500 Grade B" Weight 54.74 lbs//4.

c.

	b. Ri	ser:
	(1) Size 10,75 Wall Thickness ,500 Grade "B" Weight 54.74 lbsf
	(2) Size Wall Thickness Grade Weight
	c. Su	bsea valve assembly:
	(1) Size Wall Thickness Grade Weight
) Size Wall Thickness Grade Weight
3.	Water	depth: Maximum $\frac{-/83'}{}$ Minimum $\frac{-/83'}{}$
4.	Type o	f corrosion protection:
	a.	Impressed current system
	<u>6.</u>	Sacrificial anode system
		(1) Type of anode GAL Valum III
		(2) Spacing interval 480
		(3) Weight of unit anode given by applicant 64ll -
	M/Ac.	If platform anodes are used, are they considered adequate?
		Yes No
	Ld.	If pipeline anodes are used:
		Formula: LEp/1 = 3.82 x 104 x WO/DIR = 38300 x 64/10.75 x 480 x 7.6 = 6
		Does the calculated life expectancy equal or exceed 20 years?
		Yes No No
15.		ption of protective coating:
	a. Pi	peline Mastic of Concrete
	b. Ri	ser Zinc Primer & Epoky
	c. Su	bsea valve assembly
<u>6</u> .		ption of weighted coating:
	V	e-concrete coating Mostic
		nsity of concrete 140 PCF
		ickness of concrete/ "
	d Th	ickness of asphalt /2"

Calcula	ate the specific gravity using one of the following formulae:
a. For	r epoxy coating: $SG = 2.865W/D^2$
b. De	nsity comparison with fluid material: $SG = \frac{W+P}{\frac{A}{R}}$
Lc. Li	nes with a specific thickness of concrete:
	$SG = \frac{RC}{R} + \frac{K_a}{(T-K_1)^2} \left(\frac{W+P}{K_s} - \frac{RC}{R} \right) = \frac{-1.45}{3} = 1.66$ See attachine
	nes having two coatings of enamel and a felt wrap, or only phaltmastic coating:
	$SG = \frac{W+P}{K_a}$
RC K ₁ T W P R	ere: SG = specific gravity = density of concrete (lb/cu. ft.) , K _a , K _b = coefficients = thickness of concrete coating (inches) = weight of bare pipe (lb/ft) = weight of coating = density of fluid material (lb/cu. ft.); i.e., sea water = 64 lbs/cu. ft. = diameter of pipe (inches) = Cross-sectional area
8. Given	specific gravity
a. /, L	45 b. 1.57 c. 1.67
9. Gravit	y or density of product 60 4.75 (condensate
	capacity of pipeline DOMM CFD
	Hydrostatic Test Pressure: Line Pipe 2681 Hold Time 8 hrs.
	Riser 2995 Hold Time 4 hrs.
	ended maximum hydrostatic body test for ANSI valves, flanges, and gs are as follows:
	ANSI 300 1,100 psig ANSI 400 1,450 psig ANSI 600 2,175 psig ANSI 900 3,250 psig ANSI 1,500 5,400 psig

Note: Minimum hold times gas pipeline:

Line Pipe = 8 hrs. Riser = 4 hrs.Liquid Line = 24 hrs.

Maximum Allowable Operating Pressure (MAOP) of line pipe:

MAOP = $\frac{2 \text{ st}}{D} \times F \times E \times T$ Note: F = .72a. MAOP = $\frac{2 \times 42,000 \times .365}{70.75} \times .72 \times I \times I = 3.05 \times 9.58$ b. MAOP = $\frac{2 \times 42,000 \times .438}{70.75} \times .72 \times I \times I = 3.464 \text{ PS/8}$ c. MAOP = $\frac{2 \times 35,000 \times .500}{70.75} \times .72 \times I \times I = 3.344 \text{ PS/8}$

Maximum Allowable Operating Pressure (MAOP) of riser pipe.

Note: F = .50 for risers on natural gas transmission lines.

Note: F = .60 for risers on oil pipelines.

MAOP = 2x 35,000 x.500 x.60 x/x/ = 1,954 PS18 X.50 x/x/ = 1,6 38 PS18

MAOP =

44. Maximum Allowable Operating Pressure of flanges, fittings and valves:

= 2.4 x ANSI rating = 2.4 x 600 = 1,440 psig

Maximum Allowable Operating Pressure (MAOP) of proposed pipeline as determined in accordance with Title 49 CFR Part 195 or 192, as applicable, is 1,480 psig.

Items 12., 13., and 14. above are equal to or more than the MAWP of source.

 $1.25(MSP) \le HTP \le .95$ (smaller IP @ SMYS of item 12. or Verify: 13. above)

2624602681 ≤ <u>2709</u> 1800

The recommended limit of test as a percentage of internal pressure @ minimum yield strength is equal to 95%:

IP @ SMYS =
$$\frac{2 \times s \times t}{D} = \frac{7}{2} 852$$

	•	
		6
	18. Verify MAOP does not exceed the lowest of the following:	
	a. Submerged components: HTP/1.25 = 1728.PS18	
	b. For riser: HTP/1.5 = 1,440 Psi &	
	19. Valve guards used: Yes No	
D.	Burial Requirements: Verify the pipeline is buried in area requiring burial.	
	Minimum three (3) feet below mud line to 200 ft. contour.	
E.	Pipeline Crossings:	
	M/A1. Verify there is a minimum separation of 18 inches between the two 1	ines
	MA2. Cement bags placed two (2) feet horizontally on each side of propos pipeline.	≥d
	MA3. Crossings in water depths exceeding 200 feet:	
	a. Cement bags placed on a slope not to exceed one (1) foot vertical and two (2) feet horizontal.	
F.	Construction Information:	
	L. Proposed construction commences date July 1,1980	-
	12. Method of construction Lay Borge	
	La. Method of burial Jet Bury Bouge	
	14. Time required to lay pipe <u>Jucks</u>	
	15. Time required to complete project 4 washes	
G.	Applicant complies with current OCS pipeline guidelines:	
	Yes No	
н.	Applicant agrees to forward "as-built" drawings and hydrostatic test data within ninety (90) days after completion:	
	Yes No	

OCS-G 4305

3-17-80

C.7.c

$$SG = \frac{RC}{R} + \frac{k_1}{(T-k_1)^2} \left(\frac{W+P-RC}{K_3} - \frac{RC}{R} \right)$$

$$-2.1875 + \frac{34.52}{(6.83)^2} \left(\frac{57.05}{48.19} - 2.1875 \right)$$

$$-2.1875 + 17427$$

$$SG = 1.45$$

(2)
$$SG = 2.1875 + .7400 \left(\frac{48.19 + 16.57}{48.19} - 2.1875 \right)$$

$$=2.1875 - 16243$$


PIPELINE APPLICATION CHECK LIST

INSTRUCTIONS: Check the blank on the left if the statement is affirmative or correct data submitted. Make N/A (not applicable) where appropriate. Place an X in the blank if the answer is no or if the data was not submitted. All blanks marked X must be rectified to a check (or qualified) before approval can be given for the pipeline. Enter data in the blanks furnished.

HUSSEN HERMATODOST ABUSEN HERMATODOST HUSSEN 287
G 3951 A. Verrity the fortowing general information. April 1. SOP
a. Do the leases involved on the P/L application appear on the current Suspension of Production (SOP) Lease List?
N. POD
a. Is the pipeline presently covered by an approved Plan of Development (POD)?
III. Lease Stipulation Yes No If yes, does lease require an archaeological survey? Yes No
IV. USGS Application
a. The applicant is a Federal lease holder and the pipeline is to be used for such purposes as:
1. Moving production to a control point for gathering, treating storing, or measuring.
2. Delivery of production to a point of sale.
3. Delivery of production to a pipeline operated by a transportation company
4. Moving fluids in connection with lease operations, such as for injection purposes.
b. The pipeline is within the lease coundary owned by the operator.
c. Pipeline is within contiguous lease coundaries.
d. Pipeline is within noncontiguous lease boundaries. (Note: Items b, c, and d all fall under 30 CFR 250.18)
e. Lessee's "intent to cross" letters are received. (Wait 30 days for letters of objection. Only objections concerning interference with lease operations will be considered.)
f. Pursuant to Secretarial Order 2974 of April 30, 1975, check the following:
we /
uu.

		1. FWS notified
		2. FWS comment received
		_ 3. BLM notified
		4. BLM comment received
		5. Environmental Impact Evaluations completed
		6. If related to new POD/P, date of POD/P approval
Ÿ.	BLM	Application
	а.	The pipeline must not be a gathering line.
VI.	DOT	Pipelines
<u>/</u>	a.	The pipelines are shoreward of the outlet flange at the last process facility (If yes, include 49 CFR 192 for gas P/L or 49 CFR 195 for oil P/L in approval.)
/II.	DOI	Pipelines

Ala a. Pipelines not covered by VI above.



C.	Ver:	ify	that the <u>location plat</u> depicts the following:
	_	ı.	Location of pipeline
	<u>/</u> :	II.	Length of pipeline
_/	<u>/</u> 1:	Π.	Size of pipeline
	<u>_</u> ;	īv.	Type of service
	_	v.	Direction of flow
	<u>/</u>	/I.	X-Y coordinates of key ponts
D.			that the information given on the submitted data sheet is completed; culate the MAOP sc, MAOP p/1.
	I.	Gen	eral information for calculating MAOP _{sc} , MAOP _{rc} , etc.
		а.	3256 3422 2852 Size of pipeline, inches 10.75
		ъ.	Weight of pipeline, lbs./ft. 54.74 48.19 40.49
		с.	Grade of pipeline B X42 X42
		d.	Wall thickness, inches
		е.	Size of riser, inches 10.75
		f.	Weight of riser, 1bs./ft. 64.74
		g.	Grade of riser
		h.	
			Wall thickness of riser, inches 0.5
		i.	Minimum WP rating of piping, fittings, valves, psig 1440
		j.	Hydrostatic test pressure (HTP), psig 2624-2681 mag 2895-3060 Hold time, hrs. Shua 4hua
		k.	
		1.	Classification of pipeline (oil or gas)
		m.	Type of pipe (ASTM A-106, API-5L, etc.) NOTE: If ASTM A-53 Reference API RP 14E, Section 2.1.a(2)

II. DOI Pipelines

- a. IP @ SMYS for submerged pipeline = 2st 2952
- b. (.72 x IP @ SMYS) for submerged pipeline = $\frac{70.53}{\text{sc}}$ (MAOP_{sc})
- c. IP @ SMYS for riser = $\frac{2st}{D}$ = $\frac{325}{5}$
- d. (.60 x IP $\stackrel{\bullet}{\bullet}$ SMYS) for riser = _____ (MAOP_{rc})
- e. See Ii above $(MAOP_{pfv}) =$ $(MAOP_{pfv})$
- f. Is 1.25 MSP $\stackrel{\checkmark}{=}$ ATP $\stackrel{\checkmark}{=}$.95 (IP @ SMYS for smaller IP of a and c above)
- ____g. HTP/1.25 = ____
- ___h. Is HTP hold time $\stackrel{?}{=}$ 2 hours
- ____i. MAOP of receiving pipeline from IV _____
- j. MAOP = the smallest of α , d, e, g, and i above
- (MAOP_{p/1}) .
- k. Test pressure ANSI & API carbon steel RTJ & RF Flanges and Valves
 - (From Table 3.1, Page 31 API RP 14L)
- 1. Is K ➤ HTP

NOTE: If note, add statement in approval letter to insure valves and flanges are note subjected to test pressure.

___m. Is j≥MSP

If not, one of the following is necessary:

.:> _

- $\underline{\hspace{1cm}}$ \hbar . Redundant safety equipment is afforded.
- 2. A departure from the requirement for redundant safety equipment

			_
III.	DOT	Pipel	ines

a. IP @ SMYS for submerged pipeline =
$$\frac{2st}{D}$$
 = 2852.

c. IP @ SMYS for riser =
$$\frac{2st}{D}$$
 = 325%

d. For oil P/L (.60 x IP @ SMYS) for riser =
$$\frac{3256}{1628}$$
 (MAOP_{rc})
For gas P/L (.50 x IP @ SMYS) for riser = $\frac{1628}{1628}$

f. Limit of Testing

NA 1. For oil P/L

Is 1.25 MSP $\stackrel{\leq}{=}$ HTP $\stackrel{\leq}{=}$.95 (IP @ SMYS for smaller IP of a and c above)

2. For gas P/L riser component:

3. For gas P/L submerged component:

Is 1.25 MSP = HTP of submerged component = .95 (IP @ SMYS of a above

g. $MAOP_{p/1}$ based on HTP

2. For gas P/L riser component
$$HTP/1.5 = 1997$$
 of riser


3. For gas P/L submerged component HTP/1.25 = 2099 of submerged component

N	/h.	For oil P/L Is HTP hold time $\stackrel{?}{=}$ 24 hours \mathcal{N}/\mathcal{A}
		For gas P/L Is HTP hold time 2 8 hours
	i.	MAOP of receiving pipeline from IV
	j.	$MAOP_{p/1}$ = the smallest of b, d, e, g, and i above
		(MAOP _{p/1})
	k.	Test pressure ANSI & API carbon steel RTJ & RF flanges and valves
		2175 (From table 3.1, page 31 API RP 14E)
	1.	Is k > HTP NO
Jusent	^	NOTE: If not, add statement in approval letter to insure valves and flanges are not subjected to test pressure.
Jur	m.	Is j Z MSP
•		<u> </u>
		If not, one of the following is necessary:
		1. Redundant safety equipment is afforded
	-	2. A departure from the requirement for redundant safety equipment.

IV.	Pipeline	Receiving	Production	(Installed	Prior	to	July	31,	1977)
-----	----------	-----------	------------	------------	-------	----	------	-----	-------

		Submerged Component	. Riser				
a.	Size, inches	_ 30" HIOS	· · · · · · · · · · · · · · · · · · ·				
ъ.	Grade		-				
c.	Wall thickness, inches	3					
d.	Minimum working pres- sure of valves and flanges	-47	(MAOPpfv)				
e.	Date of last hydro- static test		· · · · · · · · · · · · · · · · · · ·				
f.	HTP, psig						
g.	Hold time, hrs.						
h.	MAOP based on HTP HTP/1.25						
i.	IP@SMYS for submer- ged P/L 2ST/D						
j.	<pre>(.72 x IP@SMYS) for submerged P/L</pre>		(MAOPsc)				
k.	IP@SMYS for riser 2ST/D						
1.	(.60 x IP@SMYS) for riser		(MAOPrc)				
m.	If the receiving P/L is a DOT gas P/L and has not been tested since July 1, 1971, then what is the HAOP to which the segment was subjected during the 5 years prior to July 1, 1976?						
n.	MAOP of receiving P/L2 MAOP of proposed P/L MSP of proposed P/L						
	7		7				

^{*}HAOP - Highest actual operating pressure



F. Verify that the information given on the submitted data sheet is complete; and calculate the specific gravity on the pipeline (SP_{p/1})

I. General Information pertaining to SG_{p/1}

a. Description of pipelines protective coating ______

b. Description of risers protective coating _____

c. Description of pre-concrete coating _____

d. Density of concrete, lbs./cu. ft. _____/40

e. Thickness of concrete, inches _______

f. Thickness of asphalt/somastic ______/\frac{1}{2}

g. Gravity or density of products:

For gas ________ (air = 1.0)

For oil/condensate ________ OAPI, ________ (water = 1.0)

h. Given SG_{p/1} ________

, 365 1.45 , 438 1.57 ,500 1.67

II. SG_{p/1}

Wa. Expoxy-coated pipelines:

$$SG_{p/1} = 2.865 \text{ W/D}^2$$

W = weight of bare pipe, lbs./ft.

D = diameter of pipe, inches

b. For weighted pipelines:

$$SG_{p/1} = \frac{dc}{d} + \left[\frac{k_2}{(T-k_1)^2} - \frac{dc}{k_3}\right]$$

dc = density of concrete, lbs./ft/3

d = density of fluid in which pipeline is submerged, 1bs./ft.3

 k_1 , k_2 , k_3 = coefficients from tables


T = thickness of concrete coating, inches

W = weight of bare pipe, lbs./ft.

P = weight of double enamel coat and felt wrap, or weight of asphaltmastic coating, lbs./ft.

$$SG_{p/1} =$$

c. Is our calculated SG = operator's given SG



NOTE: These values should be approximately the same. If not, resolve. If the SG is close to a value of 1, the pipeline is unacceptable and must be weighted with concrete or anchored securely to the bottom.

- G. Verify the following general information:
 - I. Water Depth, ft. 183 (Max) (Min)

 II. Burial Depth, ft. 3'

 - III. Maximum Operating Pressure (MOP) 750-1200
 - IV. Capacity 38 MINCED MOT 1002 OUTLET 1000
 - V. No. of lines: Existing Proposed